OFFICE OF THE PRINCIPAL BIHAR NATIONAL COLLEGE

PATNA UNIVERSITY. PATNA

EMERGENT NOTICE INVITING QUOTATION

Quotation No: PL-81 24

Date: 21 02 25

NAME OF WORK: REPAIR AND PAINTING OF DEPARTMENT OF B.C.A. B.N. COLLEGE, PATNA

Sealed quotations are invited in prescribed format for this work. For details terms and condition, please visit the office of the undersigned on any working days from 10.30 A.M. to 5.00 P.M Prscribed format may also be downloaded from the website of B.N. College, Patna.

Designation of officer inviting quotation	The Principal, B.N. College, Patna
Place, Time & Date of receiving of quotation	Office of the Principal, B.N. College, Patna up to 3.00 p.m. on 25.02.2025
Place, Time & Date of opening quotation	Office of the Principal, B.N. College, Patna at 3.30 p.m. on 25.02.2025.

PRESCRIBED FORMAT

S.N.	Description	Quantity		Unit	Rate	Amount
J.14.		Que	iritity	Offic	(Rs.)	
1	Providing skilled labour for removing grown plants over roof and external walls of building along with cleaning roof, as per direction of Engineer-in-charge.	2	Day	Day		
2	Providing and fixing on wall face unplastidsed-PVC(working pressure 4 kgf per sqm) rain water pipes conforming to IS:4985 including jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion.110 mm diameter	6	m	m		
3	Providing and fixing on wall face unplasticised -PVC molded fittings/accessories for unplasticised-PVC rain water pipes conforming to (S:4985 including jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion.110 mm bend	2	No	Each		
4	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.With cement mortar 1:4 (1 cement :4 fine Sand)	30	Sqm	Sqm		
5	Removing dry or oil bound distemper by scrapping, sand paper and preparing the surface smooth including necessary repari scratches etc. complete.	447	Sqm	Sqm		1000
6	Providing and applying white cement based putty of average thickness 2 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete	341	Sqm	Sqm		



110

S.N	Description Finishing walls with Acrylic Smooth exterior paint of required shade: New work (Two or more coat applied @ 1.67 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	Quantity		Unit	Rate (Amount (Rs.)
7		341	Sqm	Sqm		
8	Finishing walls with Acrylic Smooth exterior paint of required shade:Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface	136	Sqm	Sqm		
9	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:One or more coats on old work.	74	Sqm	Sqm		
10	ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / aneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-incharge. (Glazing, paneling and dash fasteners to be paid for separately):					
а	For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	17	Kg	Kg		,
b	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately)Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	25	Kg	Kg		
11	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-incharge.Pre-laminated particle board with decorative lamination on both sides	2	Sqm	Sqm		
12	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item) With float glass panes of 5.50 mm thickness(weight not less than 12.50 kg/sqm)	3	Sqm	Sqm		

De

CN	Description	Quantity		Unit	Rate	Amount
S.N.					(Rs.)	
13	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS: 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete:100 mm	11	No	Each		
14	Providing and fixing aluminium sliding door bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS: 1868), transparent or dyed to required colour or shade, with nuts and screws etc. omplete:250x16 mm	1	No	Each		
15	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS: 1868), transparent or dyed to required colour or shade, with necessary screws etc. complete:150x10 mm	10	No	Each		
16	Carriage of materials: Sone sand from Koelwar, 45 Km distance of surface road.	1	Cum	Cum		
17	Price difference of materials for Patna urban area: Ordinary Portland cement.	4	Bag	Bag		
18	Reserved price for any other un seen work.	1	L.S.	L.S.	2554	2554
	Total Amount					

Terms and conditions:

- 1 Papers to be submitted with quotation: Copies of Registration Certificate, G.S.T. Certificate, PAN, Experience, etc.
- 2 At the time of opening of quotation only participants or his single authorised representatives with outhority letter will be allowed to present.
- 3 Work must be completed within 1 month after issuance of work order.
- 4 Rate of serial number18 has been fixed as Rs.2554.
- 5 Any registered agency of Government of Bihar / C.P.W.D. /M.E.S. will be considered.
- 6 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.
- 7 All disputes, what so ever shall be referred to the sole arbitration of the Principal, B.N. College, Patna and his decision shall be final and binding on the agency.

8 The undersigned reserves the right to accept or reject any or all the quotation without assigning any reasons.

BIHAR NATIONAL COLLEGE, PATNA

pe