



OFFICE OF THE PRINCIPAL
BIHAR NATIONAL COLLEGE
PATNA UNIVERSITY. PATNA 800005

Website: www.bncollegepatna.com

EMERGENT NOTICE INVITING QUOTATION

Quotation No: PL-216/26

Date: 12/05/26

**NAME OF WORK: ROOF TREATMENT BY A.P.P. PREFABRICATED WATER PROOFING MEMBRANE
OF SOUTHERN PART OF MAIN BUILDING OF B.N. COLLEGE, P.U. PATNA**

Sealed quotations are invited in prescribed format for this work, along with the amount of Earnest Money Deposit, as mentioned in the Terms and Conditions of this notice. For details terms and condition, please visit the office of the undersigned on any working days from 10.30 A.M. to 5.00 P.M. or website of College.

Designation of officer inviting quotation	Principal, B.N. College, Patna
Place, Time & Date of receiving of quotation	Office of the Principal, B.N. College, Patna up to 3.00 p.m. on 26/05/2026.
Place, Time & Date of opening quotation	Office of the Principal, B.N. College, Patna at 3.30 p.m. on 26/05/2026.

PRESCRIBED FORMAT

S.N.	Code No	DESCRIPTION	QUANTITY		UNIT	RATE	AMOUNT
1	OL71	Providing skilled labours for removing damage sheets from Parapets, chiseling damage surfaces of roof, cleaning inlets of rain water pipes and other necessary works as per direction of Engineer-in-charge.	20	Lab./Day	Lab./Day		
2	13.13.1	20 mm cement plaster of mix ;1:3 (1 cement: 3 coarse sand)	177	Sqm	Sqm		
3	15.56.	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead	50	Sqm	Sqm		
4	13.11.2.	Cement plaster in course sand 12 mm cement plaster of mix: 1:4(1 cement :4 coarse sand)	50	Sqm	Sqm		
5	12.78.2	Providing and fixing on wall face un plastidsed-PVC (working pressure 4 kgf persqm) rain water pipes conforming to IS :4985 including jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion.110 mm diameter	30	m	m		
6	12.79.	Providing and fixing on wall face unplasticised-PVC molded fittings / accessories for unplasticised-PVC rain water pipes conforming to IS: 4985 including jointing with seal ring conforming to IS:5382 leaving10 mm gap for thermal expansion.					
a	12.79.5.2	110 mm bend	10	No	Each		
b	12.79.5.1	75 mm bend	10	No	Each		
c	12.79.3.2	Single tee with door- 110x110x110mm	5	No	Each		

PL-216/26
11-05-26

S.N.	Code	DESCRIPTION	QUANTITY		UNIT	RATE	AMOUNT	
	No					(Rs.)		
7		Carraige of materials:						
a		Sone sand from Koelwar, 45 Km distance of surface road from site	5	Cum	Cum			
8		Price difference of materials for Patna urban area: Cement.	46	Bag	Bag			
9	22.20.1	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer 3 mm thick water proofing membrane, black finished reinforced with non-woven polyester matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/ sqm by the same membrane manufacture of density at 25°C, 0.87-0.89 kg/ litre and viscocity 70-160 cps. Over the primer coat the layer of membrane shall be laid using Butane Torch and sealing all joints etc., and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 650/450N/5 cm. Tear strength in longitudinal and transverse direction as 300/250N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D - 5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane.3 mm thick.	777	Sqm	Sqm			
10	S.O.R.	Reserved price for any other unseen work.	1	L.S.	L.S.	7397	7397	
TOTAL								

TERMS & CONDITIONS

- 1 Earnest Money Deposit in the form of Bank Draft in the favour of Principal, B.N College, Patna or N.S.C./ Time Deposit of Post Office , duly pledged in the name of Principal, B.N. College, Patna @ 2% i.e.Rs.9.100/- is essentilaly required with quotations. Remaining amount of Security Deposits @ 8% of bill amount will be deducted from bill.
- 2 The rate and amount of item vide serial number 10 has been previously fixed as Rs.7,397/- only.
- 3 Work must be completed within 1 month after receiving work order.
- 4 Registered experienced agency of Government of Bihar / C.P.W.D. /M.E.S. will be considered.
- 5 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.
- 6 Xerof self attested copies of Registration Certificate, Certificate of G.S.T. registration, PAN card along with work experience certificate etc. are required with quotation.
- 7 The undersignd reserve the right to accept or reject any or all the qootations without assigning any reason.
- 8 All disputes, what so ever shall be reffered to the sole arbitration of the Principal, B.N. College, Patna and his decision shall be final and binding on the agency.

PRINCIPAL
B.N.COLLEGE, PATNA

12/05/26

P.K.A.K
11-05/26